DRAWING LIST

SHEET #	DRAWING No.	DRAWING TITLE
1	1-GI-001	COVER & INDEX OF DRAWINGS
2	1-GI-002	18th FLOOR ICRA PLAN & NOTES
3	1-LS-101	18th FLOOR ICRA PLAN & NOTES
4	1-PH-101	18th FLOOR PHASING PLAN
5	1-HA-100	SUMMARY OF ASBESTOS - THERMAL SYSTEMS INSULATION (TSI)
6	1-HA-101	SUMMARY OF ASBESTOS - DEBRIS IN CEILING PLENUM
7	1-HA-102	SUMMARY OF ASBESTOS - DEBRIS IN CEILING PLENUM
ARCHITECTURAL:		
8	1-AS-001	ARCHITECTURAL: ABBREVIATIONS, SCHEDULES, DETAILS & NOTES
9	1-ASD-101	ARCHITECTURAL: 18TH FLOOR DEMOLITION PLAN
10	1-ASD-201	ARCHITECTURAL: 18TH FLOOR REFLECTED CEILING DEMOLITION PLAN
11	1-AS-101	ARCHITECTURAL: 18TH FLOOR CONSTRUCTION PLAN
12	1-AS-102	ARCHITECTURAL: 18TH FLOOR FINISH PLAN
13	1-AS-103	ARCHITECTURAL: 18TH FLOOR FURNITURE & EQUIPMENT PLAN
14	1-AS-201	ARCHITECTURAL: 18TH FLOOR CONSTRUCTION REFLECTED CEILING PLAN
15	1-AS-501	ARCHITECTURAL: WAYFINDING & DETAILS
16	1-AS-700	ARCHITECTURAL: DETAILS & NOTES
17	1-AS-701	ARCHITECTURAL: ADA DETAILS & NOTES
STRUCTURAL:		
18	1-S-101	STRUCTURAL: 18TH FLOOR CONSTRUCTION PLAN
MECHANICAL:		
19	1-MH-001	MECHANICAL: SYMBOLS, ABBREVIATIONS & NOTES
20	1-MHD-201	MECHANICAL: 18TH FLOOR DUCTWORK DEMOLITION PLAN
21	1-MHD-202	MECHANICAL: PARTIAL 19TH FLOOR DEMOLITION PLAN
22	1-MH-101	MECHANICAL: 18TH FLOOR HYDRONIC PIPING PLAN
23	1-MH-201	MECHANICAL: 18TH FLOOR DUCTWORK PLAN
24	1-MH-202	MECHANICAL: PARTIAL 19TH FLOOR DUCTWORK PLAN
25	1-MH-501	MECHANICAL: SEQUENCE OF OPERATIONS & CONTROLS
26	1-MH-701	MECHANICAL: DETAILS
27	1-MH-702	MECHANICAL: DETAILS
28	1-MH-801	MECHANICAL: DETAILS & SCHEDULES
29	1-MH-802	MECHANICAL: SCHEDULES
PLUMBING:		
30	1-PL-001	PLUMBING: SYMBOLS, ABBREVIATIONS & NOTES
31	1-PLD-101	PLUMBING: 18TH FLOOR DEMOLITION PLAN
32	1-PL-101	PLUMBING: 18TH FLOOR PLAN
33	1-PL-601	PLUMBING: DOMESTIC, SANITARY & VENT RISER DIAGRAM
34	1-PL-701	PLUMBING: LEGEND & SCHEDULE & DETAILS
FIRE PROTECTION:		
35	1-FX-001	FIRE PROTECTION: SYMBOLS, ABBREVIATIONS, NOTES & DETAILS
36	1-FXD-201	FIRE PROTECTION: 18TH FLOOR DEMOLITION PLAN
37	1-FX-201	FIRE PROTECTION: 18TH FLOOR PLAN
ELECTRICAL:		
38	1-ES-001	ELECTRICAL: SYMBOLS, ABBREVIATIONS & NOTES
39	1-ESD-101	ELECTRICAL: 18TH FLOOR POWER & LIGHTING DEMOLITION PLAN
40	1-ESD-102	ELECTRICAL: 19TH FLOOR POWER DEMOLITION PLAN
41	1-ES-101	ELECTRICAL: 18TH FLOOR POWER PLAN
42	1-ES-102	ELECTRICAL: 19TH FLOOR POWER PLAN
43	1-ES-201	ELECTRICAL: 18TH FLOOR LIGHTING PLAN
44	1-ES-701	ELECTRICAL: LEGEND & SCHEDULE & DETAILS
45	1-ES-801	ELECTRICAL: PANEL SCHEDULES

CAMPUS SITE PLAN



SCALE: 1" = 60'

C:\Users\srb\AppData\Local\Temp\AcPublish_20188\1-GI-001.dwg 7-27-21 03:43:47 PM srb

ROOM FINISH SCHEDULE

LOCATION			WALLS				CEILING		REMARKS
ROOM NO.	ROOM NAME	AREA SQ. FT. *	NORTH FINISH	EAST FINISH	SOUTH FINISH	WEST FINISH	MATERIAL	HEIGHT	
18003W	CORRIDOR	758	CMU	CMU	CMU	CMU	LCT	9'-0"	
18003W	CORRIDOR	711	GWB	GWB	GWB	GWB	ACT	9'-0"	
18004AW	PASSAGE	88	--	--	--	--	ACT	9'-0"	
18004BW	STORAGE	79	--	--	--	--	ACT	9'-0"	
18004CW	STORAGE	92	--	--	--	--	ACT	9'-0"	
18004DW	STORAGE	132	--	--	--	--	ACT	9'-0"	
18005W	STORAGE	46	--	--	--	--	ACT	9'-0"	
18006W	B.M.S CLOSET	66	--	--	--	--	ACT	9'-0"	
18007W	ELECTRICAL CLOSET	11	--	--	--	--	ACT	9'-0"	
18010W	BREAKROOM	210	CMU	CMU	CMU	CMU	LCT	9'-6"	
18011W	RAT	229	GWB	GWB	GWB	CMU	LCT	9'-6"	SCARIFY TILE IN PREPARATION FOR PAINT
18012W	MICE	221	CMU	CMU	CMU	CMU	LCT	9'-6"	
18018AW	CLEAN STERILIZATION	320	CMU	CMU	CMU	CMU	LCT	10'-0"	
18018BW	DIRTY STERILIZATION	273	BRICK	BRICK	BRICK	BRICK	LCT	10'-0"	
18019AW	MICE	149	CMU	CMU	CMU	CMU	LCT	9'-6"	
18019BW	MICE	303	CMU	CMU	CMU	CMU	LCT	9'-6"	
18020W	CLEAN CORRIDOR	441	CMU	CMU	CMU	CMU	LCT	9'-0"	
18020W	DIRTY CORRIDOR	88	CMU	CMU	CMU	CMU	LCT	9'-6"	
18022W	GUINEA PIG	278	CMU	CMU	CMU	CMU	LCT	9'-6"	
18023W	FOOD STORAGE	53	GWB	GWB	GWB	GWB	LCT	9'-0"	
18024W	TESTING ROOM	405	GWB	GWB	GWB	GWB	ACT	9'-0"	SCARIFY TILE IN PREPARATION FOR PAINT
18025AW	WOMEN'S TOILET	195	GWB	GWB	GWB	GWB	ACT	9'-0"	
18025BW	MEN'S TOILET	195	GWB	GWB	GWB	GWB	ACT	9'-0"	
18026W	COLD STORAGE	83	CMU	GWB	CMU	CMU	ACT	9'-0"	
18029W	OFFICE	141	GWB	GWB	GWB	GWB	ACT	9'-0"	SCARIFY TILE IN PREPARATION FOR PAINT
18030W	OFFICE	145	GWB	GWB	GWB	GWB	ACT	9'-0"	SCARIFY TILE IN PREPARATION FOR PAINT
18032W	OFFICE	164	GWB	GWB	GWB	GWB	ACT	9'-0"	SCARIFY TILE IN PREPARATION FOR PAINT
18033W	OFFICE	128	GWB	GWB	GWB	GWB	ACT	9'-0"	
18034W	OFFICE	128	GWB	GWB	GWB	GWB	ACT	9'-0"	

* SQUARE FOOTAGE IS AN APPROXIMATION, CONTRACTOR TO VERIFY IN FIELD PRIOR TO BID.

FINISH SCHEDULE

SYMBOL	ITEM	MANUFACTURER	NAME	COLOR *	REMARKS
P-1	METALLIC SURFACES	STONHARD	STONGLAZE VSI	FROST	WINDOWS, DOORS & UNIT HEATER COVERS
P-2	WALL PAINT	STONHARD	STONGLAZE VSI	FROST	GYPSUM BOARD, TILE, BRICK & BLOCK WALLS
P-3	CEILING PAINT	STONHARD	STONGLAZE VSI	STONSHIELD BONE	CEILINGS
P-4	CERAMIC TILE FLOORING PAINT	STONHARD	STONGLAZE HRI	COBALT	EPOXY BASE PAINT WITH SLIP RESISTANCE
P-5	CONCRETE FLOORING PAINT	STONHARD	STONGLAZE HRI	COBALT	EPOXY BASE PAINT WITH SLIP RESISTANCE, PATCH AREAS TO SMOOTH FINISH
P-6	METALLIC SURFACES	SHERWIN WILLIAMS	SW 0059	FROSTWORK	WINDOWS & DOORS
P-7	WALL PAINT	SHERWIN WILLIAMS	SW 7621	SILVERMIST	GYPSUM BOARD, TILE, BRICK, & BLOCK WALLS
P-8	CEILING PAINT	SHERWIN WILLIAMS	---	BONE	CEILINGS

* – ALL COLOR CHOICES TO BE COORDINATED & FINALIZED BY VA COR

NOTES:

1. CONCRETE FLOOR TO WALL INTERSECTIONS AT THE NEW CHASE WALLS AND CONCRETE RAMP FLOORS SHALL INCLUDE A LAYER OF STONHARD PRIMER, TWO COATS OF A STONSHIELD AGGREGATE (ONE COAT OVER THE PRIMER AND ANOTHER COAT OVER THE UNDERCOAT), A STONSHIELD UNDERCOAT, AND A STONSHIELD SEALER. PAINT MUST BE RESISTANT TO ALL CHEMICALS. SEE MANUFACTURERS PRODUCT DATA SHEETS FOR APPLICATION INFORMATION/INSTRUCTIONS.
2. ALL PLASTER/GYPSUM BOARD AND BRICK/BLOCK WALLS, AS WELL AS ALL CERAMIC TILE WALLS, SHALL BE PATCHED AND CLEANED AS REQUIRED FOR AN EVEN SURFACE, FREE FROM ANY DEBRIS AND/OR CONTAMINANTS. WASH SURFACE WITH STONKLEEN DO9 (AN INDUSTRIAL DETERGENT), AND RINSE THOROUGHLY WITH CLEAN WATER. SEE MANUFACTURERS DATA SHEETS FOR MORE INFORMATION.
3. ALL LATEX, OIL, URETHANE OR ACRYLIC PAINTED SURFACES (CMU, CONCRETE, METAL, WALL BOARD), AS WELL AS TILED SURFACES, MUST BE HAVE THE FINISHED SURFACE MECHANICALLY ABRADED PRIOR TO APPLYING STONEGLAZE FINISH. STONEGLAZE VSR WILL BOND TO EPOXY PAINTED SURFACES WITHOUT ABRADING.
4. ALL CONCRETE (CMU) WALLS TO BE PAINTED SHALL INCLUDE A LAYER OF STONGLAZE E4 AS A PRIMER PRIOR TO APPLYING STONGLAZE VSR PAINT. SEE MANUFACTURERS PRODUCT DATA SHEETS FOR APPLICATION INFORMATION/INSTRUCTIONS.
5. ALL NEW DRYWALL SURFACES WITH UP TO A LEVEL 3 JOINT COMPOUND FINISH TO BE PAINTED SHALL BE PRIMED WITH STONHARD PRIMER 180, PRIOR TO APPLYING STONGLAZE VSR. DRYWALL SURFACES OF LEVEL 4 OR 5 DRYWALL FINISH MUST HAVE FINISH REMOVED BY MECHANICAL MEANS PRIOR TO APPLICATION OF STONEGLAZE VSR PRIMER. SEE MANUFACTURERS PRODUCT DATA SHEETS FOR APPLICATION INFORMATION/INSTRUCTIONS.
6. ALL METALLIC SURFACES TO BE PAINTED, SUCH AS WINDOWS & DOORS MUST BE SHALL INCLUDE A LAYER OF STONGLAZE E4 AS A PRIMER PRIOR TO APPLYING STONGLAZE VSR PAINT. PAINT MUST BE RESISTANT TO ALL CHEMICALS. SEE MANUFACTURERS PRODUCT DATA SHEETS FOR APPLICATION INFORMATION/INSTRUCTIONS.
7. ALL FINISHES TO BE APPLIED BY A STONHARD CERTIFIED INSTALLER ONLY.
8. CONTRACTOR SHALL TAKE ALL PRECAUTIONS TO PROPERLY VENTILATE THE SPACE DURING THE PAINTING PROCESS. ODOR MUST BE CONTROLLED TO THE BEST EXTENT FEASIBLE.

DOOR SCHEDULE

DOOR TAG	ROOM NO.	ROOM NAME	WIDTH	HEIGHT	THICKNESS	TYPE	DOOR MATERIAL	DOOR FINISH	FRAME TYPE	FRAME MATERIAL	FRAME FINISH	FIRE RATING	HARDWARE	DESCRIPTION
C03W1/V	18003W	CORRIDOR	3'-8"	7'-0"	1-3/4"	1	H.M.	MANUF.	F1	H.M.	MANUF.		HW-6	COORDINATE WITH ELECTRICAL/FIRE ALARM
C03W2/QU	18003W	CORRIDOR	2'-6"/3'-6"	7'-0"	1-3/4"	3	H.M.	MANUF.	F3	H.M.	MANUF.	–	HW-8C	
04W/S	18004AW	PASSAGE	3'-0"	7'-0"	1-3/4"	2	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-5	
05W/Q	18005W	STORAGE	2'-6"	7'-0"	1-3/4"	1	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-5	
06W/Q	18006W	BMS CLOSET	2'-6"	7'-0"	1-3/4"	1	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-5	
07W/ZZ	18007W	ELECT. CLOSET	2'-6"	6'-6"	1-3/4"	3	H.M.	MANUF.	F3	H.M.	MANUF.	–	HW-11C	
09W/Z	18009W	FIRE EXT. CAB.	2'-6"	6'-6"	1-3/4"	3	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-1N	
10W/V	18010W	BREAKROOM	3'-8"	7'-0"	1-3/4"	2	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-1A	
11W/S	18011W	RAT	3'-0"	7'-0"	1-3/4"	1	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-3	
12W/U	18012W	MICE	3'-6"	7'-0"	1-3/4"	1	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-3	
13W/N	18013W	PIPE CHASE	2'-0"	7'-0"	1-3/4"	1	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-5D	
18AW/V	18018AW	CLEAN STERILIZATION	4'-0"	7'-0"	1-3/4"	3	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-3	
18BW/V	18018BW	DIRTY STERILIZATION	4'-0"	7'-0"	1-3/4"	3	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-3	
19AW/U	18019AW	MICE	3'-6"	7'-0"	1-3/4"	1	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-3	
19BW/U	18019BW	MICE	3'-6"	7'-0"	1-3/4"	1	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-3	
C20W2/QU	18020W	DIRTY CORRIDOR	2'-6"/3'-6"	7'-0"	1-3/4"	3	H.M.	MANUF.	F3	H.M.	MANUF.	–	HW-8C	
22W/S	18022W	GUINEA PIG	3'-0"	7'-0"	1-3/4"	1	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-3	
23W/Q	18023W	FOOD STORAGE	2'-6"	7'-0"	1-3/4"	1	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-5D	
24W/V	18024W	TESTING ROOM	3'-8"	7'-0"	1-3/4"	1	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-3	
25AW/S	18025AW	WOMEN'S TOILET	3'-0"	7'-0"	1-3/4"	1	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-1A	
25BW/S	18025BW	MEN'S TOILET	3'-0"	7'-0"	1-3/4"	1	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-1A	
26W/N	18026W	COLD STORAGE	2'-0"	7'-0"	1-3/4"	1	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-5D	
29W/S	18029W	OFFICE	3'-0"	7'-0"	1-3/4"	1	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-3A	
30W/V	18030W	OFFICE	3'-8"	7'-0"	1-3/4"	1	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-3A	
32W/S	18032W	OFFICE	3'-0"	7'-0"	1-3/4"	1	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-3A	
33W/S	18033W	OFFICE	3'-0"	7'-0"	1-3/4"	1	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-3A	
34W/Q	18034W	OFFICE	2'-6"	7'-0"	1-3/4"	1	H.M.	MANUF.	F1	H.M.	MANUF.	–	HW-3A	

DOOR SCHEDULE NOTES:

1. SWING SHALL BE AS SHOWN ON PLANS.
2. DOORS AND FRAMES SHALL BE CONSTRUCTED WITH SEAMLESS CONSTRUCTION AND NO RECESSES AT TOP AND BOTTOM EDGES.
3. DOORS SHALL BE SOLID OR COMPLETED FOAM FILLED.
4. GLAZING IN GLAZING FRAMES SHALL BE FULLY SEALED.
5. PROVIDE SEALS, SWEEPS, AND OTHER DEVICES AS REQUIRED TO PROVIDE VERMIN RESISTANT DOORS AND FRAMES AT ANIMAL HOLDING ROOMS.
6. SEAL EVERY JOINT BETWEEN FRAME AND ADJACENT CONSTRUCTION, SEE SEALANT TABLE.
7. SEAL EACH SEEM BETWEEN FIXED HARDWARE AND DOOR TO WHICH IT IS APPLIED, SEE SEALANT TABLE.

ABBREVIATIONS

ACT	ACOUSTIC CEILING TILE
ACCU	AIR COOLED CONDENSING UNIT
AD	ACCESS DOOR
A.F.F.	ABOVE FINISHED FLOOR
AL	ALUMINUM
CFM	CUBIC FEET PER MINUTE
CG	CEILING GRILLE
CH	CEILING HEIGHT
CLG	CEILING
CMU	CONCRETE MASONRY UNIT
DF	DRINKING FOUNTAIN
DIV	DIVISION
DN.	DOWN
DWG	DRAWING
EA	EACH
E.C.	ELECTRICAL CONTRACTOR
ELEC.	ELECTRICAL
ELEV	ELEVATOR
EQUIP.	EQUIPMENT
EXIST	EXISTING
FLR	FLOOR
FT	FEET OR FOOT
G.C.	GENERAL CONTRACTOR
GYB	GYPSUM BOARD
H.C.	HVAC CONTRACTOR
HDR	HEADER
LF	LINEAR FEET
LVL	LAMINATED VENEER LUMBER
MAX.	MAXIMUM
MIN.	MINIMUM
MTD	MOUNTED
MTG	MOUNTING
N.I.C.	NOT IN CONTRACT
NOM.	NOMINAL
NTS	NOT TO SCALE
O.C.	ON CENTER
P.C.	PLUMBING CONTRACTOR
PSF	POUNDS PER SQUARE FT.
PSI	POUNDS PER SQUARE IN.
P.T.	PRESSURE TREATED
REQ.	REQUIRED
RM.	ROOM
R.O.	ROUGH OPENING
SCHED.	SCHEDULE
SECT.	SECTION
SPEC.	SPECIFICATION
STC	SOUND TRANSMISSION CLASS
SYS.	SYSTEM
TYP.	TYPICAL
U.O.N.	UNLESS OTHERWISE NOTED
VIF	VERIFY IN FIELD



INTERIOR DOOR FRAMES
N.T.S.

GENERAL NOTES:

1. CONTRACTOR SHALL BE RESPONSIBLE FOR CHECKING ALL DIMENSIONS ON THESE PLANS AGAINST FIELD CONDITION PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES TO THE ENGINEER. ALL DIMENSIONS AND LOCATIONS AS-INDICATED ON THE DRAWINGS SHALL BE CONSIDERED AS REASONABLY CORRECT BUT IT SHALL BE UNDERSTOOD THAT THEY ARE SUBJECT TO MODIFICATION AS MAY BE NECESSARY OR DESIRABLE AT THE TIME OF INSTALLATION TO MEET ANY UNFORESEEN OR OTHER CONDITION.
2. ALL WORK PERFORMED SHALL COMPLY WITH BUILDING AND ZONING ORDINANCE OF THE LOCAL AUTHORITY HAVING JURISDICTION, AND THE NYS BUILDING AND ENERGY CODES.
3. CONTRACTOR OR ANY SUBCONTRACTOR DOING ANY WORK UNDER THIS CONTRACT SHALL CARRY LIABILITY AND PROPERTY DAMAGE INSURANCE AGAINST ACCIDENTS OF ALL KINDS AND SHALL FURNISH OWNER WITH CERTIFICATES OF INSURANCE.
4. NEW WALL AND CEILING FINISHES SHALL HAVE A FLAME-SPREAD INDEX OF 26-75 (CLASS B) IN CORRIDORS AND EXIT ENCLOSURES, 76-200 (CLASS C) IN ROOMS AND ENCLOSED SPACES.
5. NEW FLOOR FINISHES SHALL NOT BE LESS THAN CLASS II, GREATER THAN OR EQUAL TO .22 WATTS/CM^2 (MIN. CRITICAL RADIANT FLUX) IN EXIT ENCLOSURES, PASSAGEWAYS, CORRIDORS AND ROOMS NOT SEPARATED FROM CORRIDORS. (EXISTING FLOOR FINISHES TO REMAIN.)
6. CONTRACTOR SHALL PROVIDE AND INSTALL ALL COMPONENTS INDICATED ON DETAIL SHEETS, PLANS, SPECIFICATIONS AND ALL PERTINENT EQUIPMENT REQUIRED FOR A COMPLETE AND WORKABLE SYSTEM.
7. CONTRACTOR SHALL PROTECT THE PUBLIC AND STRUCTURE DURING CONSTRUCTION WITH TEMPORARY FENCING AND BRACING.
8. CONTRACT CLOSE OUT: IN THE PRESENCE OF THE OWNER, ENGINEER OR ARCHITECT; DEMONSTRATING OPERATION OF SYSTEMS AND THAT ALL SPECIFICATIONS HAVE BEEN MET TO THE SATISFACTION OF ALL PARTIES.
9. IT IS THE INTENT AND PURPOSE OF THESE SPECIFICATIONS AND DRAWINGS TO INCLUDE AND PROVIDE FOR ALL MATERIALS, APPLIANCES AND LABOR TO PROPERLY COMPLETE AND LEAVE IN PERFECT WORKING CONDITION THE ENTIRE SYSTEM HEREINAFTER SPECIFIED. ANY MATERIAL, LABOR OR APPLIANCE NOT SPECIFICALLY MENTIONED IN THESE SPECIFICATIONS OR SHOWN ON THE DRAWINGS, BUT NECESSARY FOR A COMPLETE INSTALLATION MUST BE FURNISHED BY THIS CONTRACTOR.

DOOR MODIFICATION LEGEND

MARK	DESCRIPTION
A	LAMINATED GLASS
D	DOUBLE GLAZED, TEMPERED GLASS
F	FIRE RATED GLAZING
H	ELECTRIC HOLD
L	LOUVER
LP	LIGHT PROOF LOUVER
M	MECH. SEAL FOR LIGHT PROOF AND SOUND RETARDING DOOR
O	180 DEGREE SWING
T	TEMPERED GLASS
U	UNDERCUT 1"
V	LEAD GLASS

DOOR FINISH LEGEND

MARK	DESCRIPTION
ALUM	ALUMINUM
H.M.	HOLLOW METAL
GL	GLASS
WD	WOOD



DOOR SIZES

MK	WIDTH		HEIGHT		MK	WIDTH		HEIGHT	
	IN		IN			IN		IN	
A	1'-6"		6'-8"		N	2'-0"		7'-0"	
B	2'-0"		6'-8"		O	2'-2"		7'-0"	
C	2'-2"		6'-8"		P	2'-4"		7'-0"	
D	2'-4"		6'-8"		Q	2'-6"		7'-0"	
E	2'-6"		6'-8"		R	2'-8"		7'-0"	
F	2'-8"		6'-8"		S	3'-0"		7'-0"	
G	2'-10"		6'-8"		T	3'-4"		7'-0"	
H	3'-0"		6'-8"		U	3'-6"		7'-0"	
I	3'-2"		6'-8"		V	3'-8"		7'-0"	
J	3'-4"		6'-8"		W	3'-10"		7'-0"	
K	3'-8"		6'-8"		X	4'-0"		7'-0"	
L	3'-10"		6'-8"		Y	3'-0"		8'-0"	
M	1'-6"		7'-8"		Z	2'-6"		6'-6"	
*	1'-6"		7'-0"						

DOOR TYPE ELEVATIONS
N.T.S.



FRAME ELEVATIONS
N.T.S.



PLAN LEGEND



Wall Type B	51.7 FT
Partition Type C, 01 side GB and moist	33.2 FT
Partition Type C, 02 side GB and moist	29.0 FT
Partition Type C, 02 side GB and 01 side moist	35.0 FT
Partition Type C, 01 side GB	3.7 FT
Install new GB @ Existing wall	299.2 FT



1 18th FLOOR CONSTRUCTION PLAN
1/4" = 1'-0"

NOTE:

1. INFILL ALL UNUSED ELECTRICAL COMMUNICATION AND SWITCH LOCATIONS WITH MORTAR PRIOR TO PAINTING.

CONSTRUCTION KEYED NOTES:

1. REMOVE DOORS AND JAMBS AND REPLACE WITH NEW TO MATCH EXISTING WIDTH AND HEIGHT. ALL DOORS AND JAMBS IN ANIMAL TESTING ROOMS TO HAVE AIR TIGHT SEAL WHEN IN CLOSED POSITION.
2. COORDINATE NEW WALL LENGTH AND SOFFIT HEIGHT WITH NEW EQUIPMENT
3. CMU SOFFIT MIN. 1 COURSE ABOVE CEILING RESTING ON (2) 6x6x1/2" ANGLES. OVERLAP EACH SIDE 12" MIN. COORDINATE IN FIELD WITH NEW EQUIPMENT.
4. INFILL 48"Wx16"Hx6"D OPENING, LEFT BY REMOVED CONVECTOR, WITH CMU. MATCH EXISTING CMU SIZE AND MORTAR JOINT PATTERNS.
5. INFILL 10"Wx8"Hx6"D WALL OPENING, LEFT BY REMOVED OXYGEN ZONE VALVE BOX, WITH SOLID CMU. MATCH EXISTING CMU SIZE AND MORTAR JOINT PATTERNS.



1 CEILING TILE GRID ASSEMBLY
N.T.S.
GRIDLOCK TYPE 'SA'



2 CEILING TILE GRID WALL ASSEMBLY
N.T.S.

Standard Panel Hold Down Clip



Grip range of .750" - 1.250"

NOTE:
TILE GRIP SHALL BE LOCATED ON GRID MIDPOINT OF EACH SIDE OF 2'x2' TILE.

3 TYPICAL HOLD DOWN CLIP
N.T.S.



4 CEILING TILE GRID ASSEMBLY SECTION
N.T.S.



NOTE:
1. PUSH DOWN TILE GRIP SHALL BE MODIFIED IN FIELD BY CONTRACTOR.
2. MODIFIED TILE GRIP SHALL BE LOCATED ON GRID MIDPOINT OF 2'x2' TILE.
3. TILE SHALL BE DRILLED IN FIELD BY CONTRACTOR FOR INSTALLATION OF GRID LOCK TOGGLE CLIP.
4. ACCESS PANELS SHALL BE LOCATED IN 10-15% OF ROOM AREA WHERE INDICATED.

5 ACCESS GRID ASSEMBLY DETAIL
N.T.S.

NOTE: CEILING GRID HANGING WIRE 4'-0" ON CENTER EACH WAY (MAX.)

HANGER WIRE 12 GAUGE GALVANIZED STEEL WIRE – WRAP THREE FULL TIMES



TILE CEILING INSTALLED ELEVATION AS NOTED ON FINISH SCHEDULE

2' x 2' POLYMER CORE CEILING TILES

ALL INTERIOR CEILING FINISHES SHALL BE CLASS "A" MIN.

6 SUSPENDED CEILING DETAIL
N.T.S.



NOTE:
1. INSTALL PER ALL MANUFACTURERS RECOMMENDATIONS AND SPECIFICATION 092216.

7 HARD CEILING SUSPENSION SYSTEM
N.T.S.



ROOM PARTITIONS

NOTE:
1. CMU BLOCK FACE TEXTURE SHALL BE FINE SAND AGGREGATE OR GROUND FACE BLOCK FOR SMOOTH FINISH.
2. CMU FINISH SHALL BE SMOOTH AND IMPERVIOUS TO WATER FOR SANITATION PURPOSES.
3. FILL ALL JOINTS, SEAMS AND JUNCTIONS BETWEEN WALLS AND ABUTTING ITEMS WITH SEALANT COMPLYING WITH SEALANT TABLE.

8 WALL TYPE A
N.T.S.



NON-RATED INTERIOR PARTITION/ SHAFT WALL

9 WALL TYPE B - CHASE WALL DETAIL
N.T.S.



NON-RATED INTERIOR PARTITION

NOTE: USE MOISTURE RESISTANT GYP. BD ON WET SIDE(S).



NON-RATED INTERIOR PIPE CHASE

NOTE: USE MOISTURE RESISTANT GYP. BD ON WET SIDE(S).

10 WALL TYPE C
N.T.S.



11 MASONRY WALL OPENING
N.T.S.

TILES AND GRID ASSEMBLY BASIS OF DESIGN IS FROM:

Life Science Products, Inc.
124 Speer Road Chestertown, MD 21620
www.LSPinc.com
800-638-9874
(410)778-6474
Fax (410)778-4076