

SR #	CSI SECT	DESCRIPTION	Drawing Reference	QUANTITY	WASTAGE (10%)	QTY WITH WASTAGE	UNIT OF MEASUREMENT	UNIT COST	TOTAL ITEM COST	TOTAL TRADE COST
DIV 04 MASONRY										\$ 368,166
CELLAR										
Type : W05										
1		Spray applied to open cell insulation		23	8%	24.84	sf	\$ 2	\$ 50	
2		8" CMU		23	8%	24.84	sf	\$ 17	\$ 422	
3		2" min. air space, 4" max.		23	8%	24.84	sf	\$ 17	\$ 422	
4		Modular brick, common bond		23	8%	24.84	sf	\$ 28	\$ 696	
5		7/8" hat channel		23	8%	24.84	sf	\$ 28	\$ 696	
6		Block sealer		23	8%	24.84	sf	\$ 28	\$ 696	
Type : W09										
7		Modular brick, common bond		366	8%	395.28	sf	\$ 28	\$ 11,068	
8		Flexible masonry clip		366	8%	395.28	sf	\$ 28	\$ 11,068	
9		2 layers 60 min. grade 'D' building paper		366	8%	395.28	sf	\$ 2	\$ 791	
1st floor										
Type : W05										
10		Spray applied to open cell insulation		100	8%	108.00	sf	\$ 2	\$ 216	
11		8" CMU		100	8%	108.00	sf	\$ 17	\$ 1,836	
12		2" min. air space, 4" max.		100	8%	108.00	sf	\$ 17	\$ 1,836	
13		Modular brick, common bond		100	8%	108.00	sf	\$ 28	\$ 3,024	
14		7/8" hat channel			8%		sf	\$ 28	\$ 3,024	
15		Block sealer		100	8%	108.00	sf	\$ 28	\$ 3,024	
Type : W06										
16		Expanded metal lath		1,035	8%	1,117.80	sf	60	\$ 3,024	
17		8" CMU		1,035	8%	1,117.80	sf	\$ 17	\$ 19,116	
18		Thick brick veneer o/ mortar bed		1,035	8%	1,117.80	sf	\$ 28	\$ 31,298	
19		Block sealer		1,035	8%	1,117.80	sf	\$ 28	\$ 31,298	
Type : W09										
20		Modular brick, common bond		540	8%	583.20	sf	\$ 28	\$ 16,330	
21		Flexible masonry clip		540	8%	583.20	sf	\$ 28	\$ 16,330	
22		2 layers 60 min. grade 'D' building paper		540	8%	583.20	sf	\$ 2	\$ 1,166	
Type : W14										
23		8" CMU		71	8%	76.28	sf	\$ 17	\$ 12,962	
2nd floor										
Type : W05										
24		Spray applied to open cell insulation		100	8%	108.00	sf	\$ 2	\$ 216	
25		8" CMU		100	8%	108.00	sf	\$ 17	\$ 1,836	
26		2" min. air space, 4" max.		100	8%	108.00	sf	\$ 17	\$ 1,836	
27		Modular brick, common bond		100	8%	108.00	sf	\$ 28	\$ 3,024	
28		7/8" hat channel			8%		sf	\$ 28	\$ 2,400	
29		Block sealer		100	8%	108.00	sf	\$ 28	\$ 2,400	
Type : W06										
30		Expanded metal lath		926	8%	1,000.08	sf	\$ -	\$ -	
31		8" CMU		926	8%	1,000.08	sf	\$ 17	\$ 17,001	
32		Thick brick veneer o/ mortar bed		926	8%	1,000.08	sf	\$ -	\$ -	
33		Block sealer		926	8%	1,000.08	sf	\$ -	\$ -	
Type : W09										
34		Modular brick, common bond		620	8%	669.60	sf	\$ 28	\$ 18,749	
35		Flexible masonry clip		-	8%		sf	\$ -	\$ -	
36		2 layers 60 min. grade 'D' building paper		620	8%	669.60	sf	\$ 2	\$ 1,339	
Type : W14										
37		8" CMU		706	8%	762.48	sf	\$ 17	\$ 12,962	
3rd floor										
Type : W05										
38		Spray applied to open cell insulation		100	8%	108.00	sf	\$ 2	\$ 216	
39		8" CMU		100	8%	108.00	sf	\$ 17	\$ 1,836	
40		2" min. air space, 4" max.		100	8%	108.00	sf	\$ -	\$ -	
41		Modular brick, common bond		100	8%	108.00	sf	\$ 28	\$ 3,024	
42		7/8" hat channel		-	8%		sf	\$ -	\$ -	
43		Block sealer		100	8%	108.00	sf	\$ -	\$ -	
Type : W06										
44		Expanded metal lath		926	8%	1,000.08	sf	\$ -	\$ -	
45		8" CMU		926	8%	1,000.08	sf	\$ 17	\$ 17,001	
46		Thick brick veneer o/ mortar bed		926	8%	1,000.08	sf	\$ -	\$ -	
47		Block sealer		926	8%	1,000.08	sf	\$ -	\$ -	
Type : W09										
48		Modular brick, common bond		503	8%	543.24	sf	\$ 28	\$ 15,211	
49		Flexible masonry clip		-	8%		sf	\$ -	\$ -	
50		2 layers 60 min. grade 'D' building paper		503	8%	543.24	sf	\$ 2	\$ 1,086	
Type : W14										
51		8" CMU		666	8%	719.28	sf	\$ 17	\$ 12,228	

SR #	CSI SECT	DESCRIPTION	Drawing Reference	QUANTITY	WASTAGE (10%)	QTY WITH WASTAGE	UNIT OF MEASUREMENT	UNIT COST	TOTAL ITEM COST	TOTAL TRADE COST
Type : W05										
52		Spray applied to open cell insulation		100	8%	108.00	sf	\$ 2	\$ 216	
53		8" CMU		100	8%	108.00	sf	\$ 17	\$ 1,836	
54		2" min. air space, 4" max.		100	8%	108.00	sf	\$ -	\$ -	
55		Modular brick, common bond		100	8%	108.00	sf	\$ 28	\$ 3,024	
56		7/8" hat channel		100	8%	108.00	sf	\$ -	\$ -	
57		Block sealer		100	8%	108.00	sf	\$ -	\$ -	
Type : W06										
58		Expanded metal lath		926	8%	1,000.08	sf	\$ -	\$ -	
59		8" CMU		926	8%	1,000.08	sf	\$ 17	\$ 17,001	
60		Thick brick veneer o/ mortar bed		926	8%	1,000.08	sf	\$ -	\$ -	
61		Block sealer		926	8%	1,000.08	sf	\$ -	\$ -	
Type : W09										
62		Modular brick, common bond		503	8%	543.24	sf	\$ 28	\$ 15,211	
63		Flexible masonry clip		503	8%	543.24	sf	\$ -	\$ -	
64		2 layers 60 min. grade 'D' building paper		503	8%	543.24	sf	\$ 2	\$ 1,086	
Type : W14										
65		8" CMU		666	8%	719.28	sf	\$ 17	\$ 12,228	
Type : W07										
66		Expanded metal lath		1,154	8%	1,246.32	sf	\$ -	\$ -	
67		8" CMU		1,154	8%	1,246.32	sf	\$ 17	\$ 21,187	
68		Corrugated metal panel		1,154	8%	1,246.32	sf	\$ -	\$ -	
69		7/8" hat channel		1,154	8%	1,246.32	sf	\$ -	\$ -	
70		Block sealer		1,154	8%	1,246.32	sf	\$ -	\$ -	
71		Spray applied to open cell insulation		1,154	8%	1,246.32	sf	\$ 2	\$ 2,493	
Type : W14										
72		8" CMU		672	8%	729.00	sf	\$ 17	\$ 12,393	
ROOF										
Type : W07										
73		Expanded metal lath		850	8%	918.00	sf	\$ -	\$ -	
74		8" CMU		850	8%	918.00	sf	\$ 17	\$ 15,606	
75		Corrugated metal panel		850	8%	918.00	sf	\$ -	\$ -	
76		7/8" hat channel		850	8%	918.00	sf	\$ -	\$ -	
77		Block sealer		850	8%	918.00	sf	\$ -	\$ -	
78		Spray applied to open cell insulation		850	8%	918.00	sf	\$ 2	\$ 1,836	
SUB TOTAL								\$	368,166	\$ 368,166
OVERHEAD & PROFIT (25%)								25%	\$ 92,042	\$ 92,042
TOTAL BID								\$	460,208	\$ 460,208
PREPARED FOR :										
PREPARED BY :										
Notes										
This estimate is based on real market prices that are regularly updated by our team persons through market surveys.										