

SR #	CSI SECT	DESCRIPTION	Drawing Reference	QUANTITY	WASTAGE (10%)	QTY WITH WASTAGE	UNIT OF MEASUREMENT	UNIT COST	TOTAL ITEM COST	TOTAL TRADE COST
DIV 03 CONCRETE										\$ 126,312
REBARS										
COLUMNS										
Column #1										
1		24"x12" Concrete Column		4	5%	4	CY	\$ 180.00	\$ 798.00	
Shear Reinforcement:										
2		Ties Rebars- #4		381	5%	400	LBs	\$ 0.72	\$ 287.85	
3		Rebars- #7		613	5%	644	LBs	\$ 0.72	\$ 463.58	
4		Rebars- #9		204	5%	214	LBs	\$ 0.72	\$ 154.22	
5		5/8" Dia x22-1/2"Hx84"L		24	0%	24	EA	\$ 18.00	\$ 432.00	
Main Reinforcement:										
6		6-#7 Bars		699	5%	734	LBs	\$ 0.72	\$ 528.48	
Column #2										
7		24"x12" Concrete Column		6	5%	7	CY	\$ 180.00	\$ 1,190.00	
Shear Reinforcement:										
8		Ties Rebars- #4		568	5%	596	LBs	\$ 0.72	\$ 429.26	
9		Rebars- #7		920	5%	966	LBs	\$ 0.72	\$ 695.37	
10		Rebars- #9		357	5%	375	LBs	\$ 0.72	\$ 269.89	
Main Reinforcement:										
11		6-#7 Bars		1042	5%	1095	LBs	\$ 0.72	\$ 788.08	
Column #3										
12		24"x12" Concrete Column		6	5%	7	CY	\$ 180.00	\$ 1,190.00	
Shear Reinforcement:										
13		Ties Rebars- #4		568	5%	596	LBs	\$ 0.72	\$ 429.26	
14		Rebars- #7		871	5%	914	LBs	\$ 0.72	\$ 658.28	
15		Rebars- #9		245	5%	257	LBs	\$ 0.72	\$ 185.07	
Main Reinforcement:										
16		6-#7 Bars		1042	5%	1095	LBs	\$ 0.72	\$ 788.08	
Column #4										
17		24"x12" Concrete Column		6	5%	7	CY	\$ 180.00	\$ 1,190.00	
Shear Reinforcement:										
18		Ties Rebars- #4		568	5%	596	LBs	\$ 0.72	\$ 429.26	
19		Rebars- #7		871	5%	914	LBs	\$ 0.72	\$ 658.28	
20		Rebars- #9		245	5%	257	LBs	\$ 0.72	\$ 185.07	
Main Reinforcement:										
21		6-#7 Bars		1042	5%	1095	LBs	\$ 0.72	\$ 788.08	
Column #5										
22		24"x12" Concrete Column		5	5%	6	CY	\$ 180.00	\$ 1,029.00	
Shear Reinforcement:										
23		Ties Rebars- #4		491	5%	516	LBs	\$ 0.72	\$ 371.18	
24		Rebars- #7		601	5%	631	LBs	\$ 0.72	\$ 454.31	
25		Rebars- #9		316	5%	332	LBs	\$ 0.72	\$ 239.05	
26		5/8" Dia x22-1/2"Hx84"L		8	0%	8	EA	\$ 18.00	\$ 144.00	
Main Reinforcement:										
27		6-#7 Bars		901	5%	946	LBs	\$ 0.72	\$ 681.46	
Column #6										
28		24"x12" Concrete Column		5	5%	6	CY	\$ 180.00	\$ 1,029.00	
Shear Reinforcement:										
29		Ties Rebars- #4		491	5%	516	LBs	\$ 0.72	\$ 371.18	
30		Rebars- #7		392	5%	412	LBs	\$ 0.72	\$ 296.69	
Main Reinforcement:										
31		6-#7 Bars		901	5%	946	LBs	\$ 0.72	\$ 681.46	
Column #7										
32		24"x12" Concrete Column		6	5%	7	CY	\$ 180.00	\$ 1,190.00	
Shear Reinforcement:										
33		Ties Rebars- #4		568	5%	596	LBs	\$ 0.72	\$ 429.26	
34		Rebars- #7		1719	5%	1805	LBs	\$ 0.72	\$ 1,299.57	
35		Rebars- #9		666	5%	700	LBs	\$ 0.72	\$ 503.80	
36		5/8" Dia x22-1/2"Hx84"L		60	0%	60	EA	\$ 18.00	\$ 1,080.00	
Main Reinforcement:										
37		6-#7 Bars		1042	5%	1095	LBs	\$ 0.72	\$ 788.08	
Column #8										
38		24"x12" Concrete Column		2	5%	2	CY	\$ 180.00	\$ 401.80	
Shear Reinforcement:										
39		Ties Rebars- #4		192	5%	201	LBs	\$ 0.72	\$ 144.94	
40		Rebars- #7		286	5%	300	LBs	\$ 0.72	\$ 216.34	
41		Rebars- #9		476	5%	500	LBs	\$ 0.72	\$ 359.86	
42		Rebars- #10		775	5%	813	LBs	\$ 0.72	\$ 585.55	
Main Reinforcement:										
43		6-#7 Bars		352	5%	370	LBs	\$ 0.72	\$ 266.09	
Column #9										

SR #	CSI SECT	DESCRIPTION	Drawing Reference	QUANTITY	WASTAGE (10%)	QTY WITH WASTAGE	UNIT OF MEASURE	UNIT COST	TOTAL ITEM COST	TOTAL TRADE COST
44		24"x12" Concrete Column		2	5%	2	CY	\$ 180.00	\$ 401.80	
		Shear Reinforcement:								
45		Ties Rebars- #4		192	5%	201	LBs	\$ 0.72	\$ 144.94	
46		Rebars- #7		322	5%	338	LBs	\$ 0.72	\$ 243.38	
47		Rebars- #9		595	5%	625	LBs	\$ 0.72	\$ 449.82	
48		Rebars- #10		1506	5%	1581	LBs	\$ 0.72	\$ 1,138.66	
49		5/8" Dia x22-1/2"Hx84"L		24	0%	24	EA	\$ 18.00	\$ 432.00	
		Main Reinforcement:								
50		6-#7 Bars		352	5%	370	LBs	\$ 0.72	\$ 266.09	
		Column #10								
51		24"x12" Concrete Column		2	5%	2	CY	\$ 180.00	\$ 401.80	
		Shear Reinforcement:								
52		Ties Rebars- #4		192	5%	201	LBs	\$ 0.72	\$ 144.94	
53		Rebars- #7		322	5%	338	LBs	\$ 0.72	\$ 243.38	
54		Rebars- #9		966	5%	1014	LBs	\$ 0.72	\$ 729.99	
55		5/8" Dia x22-1/2"Hx84"L		36	0%	36	EA	\$ 18.00	\$ 648.00	
		Main Reinforcement:								
56		6-#7 Bars		352	5%	370	LBs	\$ 0.72	\$ 266.09	
		Column #11								
57		24"x12" Concrete Column		5	5%	6	CY	\$ 180.00	\$ 1,029.00	
		Shear Reinforcement:								
58		Ties Rebars- #4		491	5%	516	LBs	\$ 0.72	\$ 371.18	
59		Rebars- #7		613	5%	644	LBs	\$ 0.72	\$ 463.58	
60		Rebars- #9		163	5%	171	LBs	\$ 0.72	\$ 123.38	
		Main Reinforcement:								
61		6-#7 Bars		901	5%	946	LBs	\$ 0.72	\$ 681.46	
		Column #12								
62		24"x12" Concrete Column		1	5%	1	CY	\$ 180.00	\$ 246.12	
		Shear Reinforcement:								
63		Ties Rebars- #4		117	5%	123	LBs	\$ 0.72	\$ 88.78	
64		Rebars- #7		49	5%	52	LBs	\$ 0.72	\$ 37.09	
		Main Reinforcement:								
65		6-#7 Bars		216	5%	226	LBs	\$ 0.72	\$ 162.99	
		Column #13								
66		24"x12" Concrete Column		2	5%	2	CY	\$ 180.00	\$ 401.80	
		Shear Reinforcement:								
67		Ties Rebars- #4		192	5%	201	LBs	\$ 0.72	\$ 144.94	
68		Rebars- #7		322	5%	300	LBs	\$ 0.72	\$ 216.34	
		Main Reinforcement:								
69		6-#7 Bars		352	5%	370	LBs	\$ 0.72	\$ 266.09	
		Column #14								
70		24"x12" Concrete Column		2	5%	2	CY	\$ 180.00	\$ 401.80	
		Shear Reinforcement:								
71		Ties Rebars- #4		192	5%	201	LBs	\$ 0.72	\$ 144.94	
72		Rebars- #7		589	5%	618	LBs	\$ 0.72	\$ 445.04	
73		Rebars- #10		634	5%	666	LBs	\$ 0.72	\$ 479.44	
74		5/8" Dia x22-1/2"Hx84"L		12	0%	12	EA	\$ 18.00	\$ 216.00	
		Main Reinforcement:								
75		6-#7 Bars		352	5%	370	LBs	\$ 0.72	\$ 266.09	
		Column #15								
76		24"x12" Concrete Column		2	5%	2	CY	\$ 180.00	\$ 401.80	
		Shear Reinforcement:								
77		Ties Rebars- #4		192	5%	201	LBs	\$ 0.72	\$ 144.94	
78		Rebars- #7		552	5%	579	LBs	\$ 0.72	\$ 417.22	
79		Rebars- #9		2020	5%	2121	LBs	\$ 0.72	\$ 1,526.82	
80		5/8" Dia x22-1/2"Hx84"L		36	0%	36	EA	\$ 18.00	\$ 648.00	
		Main Reinforcement:								
81		6-#7 Bars		352	5%	370	LBs	\$ 0.72	\$ 266.09	
		Column #16								
82		24"x12" Concrete Column		2	5%	2	CY	\$ 180.00	\$ 401.80	
		Shear Reinforcement:								
83		Ties Rebars- #4		192	5%	201	LBs	\$ 0.72	\$ 144.94	
84		Rebars- #7		331	5%	348	LBs	\$ 0.72	\$ 250.33	
85		Rebars- #9		966	5%	1014	LBs	\$ 0.72	\$ 729.99	
86		5/8" Dia x22-1/2"Hx84"L		36	0%	36	EA	\$ 18.00	\$ 648.00	
		Main Reinforcement:								
87		6-#7 Bars		352	5%	370	LBs	\$ 0.72	\$ 266.09	
		Column #17								
88		24"x12" Concrete Column		5	5%	6	CY	\$ 180.00	\$ 1,029.00	
		Shear Reinforcement:								
89		Ties Rebars- #4		491	5%	516	LBs	\$ 0.72	\$ 371.18	
90		Rebars- #7		442	5%	464	LBs	\$ 0.72	\$ 333.78	
91		Rebars- #9		163	5%	171	LBs	\$ 0.72	\$ 123.38	

SR #	CSI SECT	DESCRIPTION	Drawing Reference	QUANTITY	WASTAGE (10%)	QTY WITH WASTAGE	UNIT OF MEASUREMENT	UNIT COST	TOTAL ITEM COST	TOTAL TRADE COST
92		Main Reinforcement: 6-#7 Bars		901	5%	946	LBs	\$ 0.72	\$ 681.46	
93		Column #18 24"x12" Concrete Column		5	5%	6	CY	\$ 180.00	\$ 1,029.00	
94		Shear Reinforcement: Ties Rebars- #4		491	5%	516	LBs	\$ 0.72	\$ 371.18	
95		Rebars- #7		331	5%	348	LBs	\$ 0.72	\$ 250.33	
96		Rebars- #9		163	5%	171	LBs	\$ 0.72	\$ 123.38	
97		Main Reinforcement: 6-#7 Bars		901	5%	946	LBs	\$ 0.72	\$ 681.46	
98		Column #19 24"x12" Concrete Column		1	5%	1	CY	\$ 180.00	\$ 246.12	
99		Shear Reinforcement: Ties Rebars- #4		117	5%	123	LBs	\$ 0.72	\$ 88.78	
100		Rebars- #7		98	5%	103	LBs	\$ 0.72	\$ 74.17	
101		Main Reinforcement: 6-#7 Bars		216	5%	226	LBs	\$ 0.72	\$ 162.99	
102		Column #20 24"x12" Concrete Column		1	5%	1	CY	\$ 180.00	\$ 246.12	
103		Shear Reinforcement: Ties Rebars- #4		117	5%	123	LBs	\$ 0.72	\$ 88.78	
104		Rebars- #7		153	5%	161	LBs	\$ 0.72	\$ 115.89	
105		Main Reinforcement: 6-#7 Bars		216	5%	226	LBs	\$ 0.72	\$ 162.99	
106		Column P-1 12"x12" Concrete Column		0	5%	0	CY	\$ 180.00	\$ 84.00	
107		Shear Reinforcement: Ties Rebars- #4		48	5%	51	LBs	\$ 0.72	\$ 36.36	
108		Rebars- #7		123	5%	129	LBs	\$ 0.72	\$ 92.72	
109		Main Reinforcement: 4-#7 Bars		91	5%	103	LBs	\$ 0.72	\$ 74.17	
110		Column P-2 24"x12" Concrete Column		0	5%	0	CY	\$ 180.00	\$ 84.00	
111		Shear Reinforcement: Rebars- #7		101	5%	109	LBs	\$ 0.72	\$ 78.81	
112		Main Reinforcement: 4-#7 Bars		91	5%	103	LBs	\$ 0.72	\$ 74.17	
113		Column P-3 24"x12" Concrete Column		0	5%	0	CY	\$ 180.00	\$ 84.00	
114		Shear Reinforcement: Rebars- #7		123	5%	129	LBs	\$ 0.72	\$ 92.72	
115		Main Reinforcement: 4-#7 Bars		98	5%	103	LBs	\$ 0.72	\$ 74.17	
116		Column P-4 24"x12" Concrete Column		0	5%	0	CY	\$ 180.00	\$ 84.00	
117		Shear Reinforcement: Rebars- #7		80	5%	84	LBs	\$ 0.72	\$ 60.27	
118		Main Reinforcement: 4-#7 Bars		98	5%	103	LBs	\$ 0.72	\$ 74.17	
119		Column P-5 24"x12" Concrete Column		0	5%	0	CY	\$ 180.00	\$ 84.00	
120		Shear Reinforcement: Rebars- #7		178	5%	187	LBs	\$ 0.72	\$ 134.44	
121		5/8" Dia x22-1/2"Hx84"L		4	0%	4	EA	\$ 18.00	\$ 72.00	
122		Main Reinforcement: 4-#7 Bars		98	5%	103	LBs	\$ 0.72	\$ 74.17	
123		Column P-6 24"x12" Concrete Column		0	5%	0	CY	\$ 180.00	\$ 84.00	
124		Shear Reinforcement: Rebars- #7		129	5%	135	LBs	\$ 0.72	\$ 97.35	
125		Main Reinforcement: 4-#7 Bars		98	5%	103	LBs	\$ 0.72	\$ 74.17	
SLABS & ASSOCIATED ITEMS										
126		8"TT Slab On Grade-SOG1 5000 PSI		335	5%	352	SF	\$ 3.60	\$ 1,266.30	
127		10 MIL Vapor Barrier		335	5%	352	SF	\$ 0.68	\$ 239.19	
128		6"TT Gravel Fill Under Slab		12	5%	13	CY	\$ 25.00	\$ 325.69	
129		Reinforcement: -#4@12" O.C EW		448	5%	470	LBs	\$ 0.72	\$ 338.36	

SR #	CSI SECT	DESCRIPTION	Drawing Reference	QUANTITY	WASTAGE (10%)	QTY WITH WASTAGE	UNIT OF MEASUREMENT	UNIT COST	TOTAL ITEM COST	TOTAL TRADE COST
130		(6"W) Concrete Stairs and 4" Concrete Slab		1	5%	1	CY	\$ 98.00	\$ 72.83	
131		6x6-W4.0xW4.0 WWR		36	5%	38	SF	\$ 0.50	\$ 18.90	
132		Reinforcement: #4 Rebars		65	5%	68	LBS	\$ 0.72	\$ 49.14	
133		400 High Density Extruded Polystyrene Insulation-5'Deep		36	5%	38	SF	\$ 3.60	\$ 136.08	
134		(3'6"W) Concrete Stairs and 4" Concrete Slab		1	5%	1	CY	\$ 98.00	\$ 56.60	
135		6x6-W4.0xW4.0 WWR		40	5%	42	SF	\$ 0.50	\$ 21.00	
136		Reinforcement: #4 Rebars		70	5%	74	LBS	\$ 0.72	\$ 52.92	
137		400 High Density Extruded Polystyrene Insulation-5'Deep		40	5%	42	SF	\$ 3.60	\$ 151.20	
138		(12"x12") Grade Beam GB-1		1	5%	1	CY	\$ 98.00	\$ 80.03	
139		Reinforcement: -2#5 Top & Bottom Bars -#4@4" O.C Stirrups		254	5%	266	LBS	\$ 0.72	\$ 191.79	
140		(24"x24") Grade Beam SB-1		2	5%	3	CY	\$ 98.00	\$ 251.53	
141		Reinforcement: -3#9 Top & Bottom Bars -#4@4" O.C Stirrups		272	5%	286	LBS	\$ 0.72	\$ 205.82	
142		10" T Concrete Slab S2-5000 PSI		6210	5%	6521	SF	\$ 6.00	\$ 39,123.00	
143		#5@12" O.C E.W T&B		13	5%	14	TONs	\$ 1,250	\$ 16,985.90	
144		Addition Reinforcement #7 and #9 Bars		1	5%	1	TONs	\$ 1,250	\$ 897.63	
STAIRS										
145		(3'0" W) Conc. Stairs Type A			10%	23	cy	\$ 180.00	\$ 4,070.00	
146		Reinforcement		2	10%	2	TONS	\$ 1,250	\$ 2,062.50	
147		(3'0" W) Conc. Stairs Type B		25	10%	27	cy	\$ 180.00	\$ 4,884.00	
148		Reinforcement		2	10%	2	TONS	\$ 1,250	\$ 2,062.50	
149		(3'0" W) Conc. Stairs Type C		4	10%	5	cy	\$ 180.00	\$ 814.00	
150		Reinforcement		0	10%	0	TONS	\$ 1,250	\$ 412.50	
151		(3'0" W) Conc. Stairs Type D		4	10%	4	cy	\$ 180.00	\$ 770.00	
152		Reinforcement		0	10%	0	TONS	\$ 1,250	\$ 275.00	
SUB TOTAL									\$ 126,312	\$ 126,312
OVERHEAD & PROFIT (25%)									25% \$ 31,578	\$ 31,578
TOTAL BID									\$ 157,890	\$ 157,890
PREPARED FOR :										
PREPARED BY :										
Notes										
This estimate is based on real market prices that are regularly updated by our team persons through market surveys.										