

SR #	CSI SECT	DESCRIPTION	Drawing Reference	QUANTITY	WASTAGE (10%)	QTY WITH WASTAGE	UNIT OF MEASURE	UNIT COST	TOTAL ITEM COST	TOTAL TRADE COST
DIV 03 CONCRETE										\$ 543,731
MAT FOUNDATIONS:										
1		24" Concrete MAT-1 Foundation-6000 PSI		361	10%	397	CY	\$ 180	\$ 71,500	
2		6" Crushed Stone Bedding		90	10%	99	CY	\$ 25	\$ 2,483	
3		Mud Slab w/ Vapor Barrier		4925	10%	5418	SF	\$ 1	\$ 4,334	
4		#9@12" O.C.E.W T&B		33	10%	36	TONs	\$ 1,250	\$ 45,581	
5		24" Concrete MAT-2 Foundation (Incl. Elevator Pit) -6000 PSI		78	10%	86	CY	\$ 180	\$ 15,400	
6		6" Crushed Stone Bedding		19	10%	21	CY	\$ 25	\$ 535	
7		Mud Slab w/ Vapor Barrier		1100	10%	1210	SF	\$ 1	\$ 968	
8		#9@12" O.C.E.W T&B		7	10%	8	TONs	\$ 1,250	\$ 9,818	
FOUNDATION WALLS:										
7		12" Concrete Wall BW-1		132	10%	145	CY	\$ 185	\$ 26,870	
8		2" XPS Insulation (R-10d)		3565	10%	3922	SF	\$ 2	\$ 7,372	
9		Preprufe 300R+Foundation Waterproofing Membrane		3565	10%	3922	SF	\$ 1	\$ 3,137	
10		Vertical Reinforcement: #6@12" O.C-Inside Face		4	10%	4	TONs	\$ 1,250	\$ 5,319	
11		#4@12" O.C-Outside Face Horizontal Reinforcement: #4@12" O.C-EA.Face		2	10%	3	TONs	\$ 1,250	\$ 3,274	
12		12" Concrete Wall BW-2		15	10%	17	CY	\$ 350	\$ 5,903	
13		2" XPS Insulation (R-10d)		414	10%	455	SF	\$ 3	\$ 1,275	
14		Preprufe 300R+Foundation Waterproofing Membrane		414	10%	455	SF	\$ 1	\$ 638	
15		Vertical Reinforcement: #7@12" O.C-Inside Face		7	10%	8	TONs	\$ 2,250	\$ 18,035	
16		#7@12" O.C-Outside Face Horizontal Reinforcement: #4@12" O.C-EA.Face		2	10%	2	TONs	\$ 2,250	\$ 5,894	
SHEARWALLS										
Shearwall SW-1 :										
17		12" Concrete Wall (Cellar to BH Roof)		100	10%	110	CY	\$ 185	\$ 20,350	
18		Reinforcement: #4@12" O.C-Horizontal			10%		TONs	\$ 1,250	\$ 6,613	
19		#4@12" O.C-Vertical Bars Reinforcement: (Zone-1) -14-#8 Bars-Vertical (Cellar to 1st Floor) -10-#8 Bars-Vertical (1st-3rd Floor) -6-#8 Bars-Vertical (3rd to BH Roof)		1	10%	1	TONs	\$ 1,250		
20		#4@12" O.C-Ties Reinforcement: (Zone-3) -8-#8 Bars-Vertical (Cellar) -6-#8 Bars-Vertical (1st-BH Roof)		1	10%	1	TONs	\$ 1,250		
21		#4@12" O.C-Ties Reinforcement: (Zone-4) -8-#8 Bars-Vertical (Cellar) -6-#8 Bars-Vertical (1st-BH Roof)		1	10%	1	TONs	\$ 1,250		
22		#4@12" O.C-Ties Reinforcement: (Zone-5) -12-#8 Bars-Vertical (Cellar) -8-#8 Bars-Vertical (1st-3rd Floor) -6-#8 Bars-Vertical (1st-BH Roof)		1	10%	1	TONs	\$ 1,250		
23		#4@12" O.C-Ties Reinforcement: (Zone-6) -14-#8 Bars-Vertical (Cellar) -10-#8 Bars-Vertical (1st-3rd Floor) -6-#8 Bars-Vertical (3rd to BH Roof)		1	10%	1	TONs	\$ 1,250		
24		#4@12" O.C-Ties			10%	1		\$	1,671	
Shearwall SW-2 :										
24		12" Concrete Wall (Cellar to 1st Floor)		2	10%	2	CY	\$ 185	\$ 452	
25		12" Concrete Wall (1st to 7th Floor)		91	10%	100	CY	\$ 185	\$ 18,451	
26		Reinforcement: #4@12" O.C-Horizontal		3	10%	4	TONs	\$ 1,250	\$ 4,607	
27		#4@12" O.C-Vertical Bars Reinforcement: (Zone-7) -8-#8 Bars-Vertical (1st-3rd Floor) -6-#8 Bars-Vertical (3rd to Roof)		1	10%	1	TONs	\$ 1,250		
28		#4@12" O.C-Ties Reinforcement: (Zone-8) -6-#8 Bars-Vertical (1st-3rd Floor) -6-#8 Bars-Vertical (3rd to Roof)		1	10%	1	TONs	\$ 1,250		
29		#4@12" O.C-Ties Reinforcement: (Zone-9) -10-#8 Bars-Vertical (1st-3rd Floor) -6-#8 Bars-Vertical (3rd to Roof)		1	10%	1	TONs	\$ 1,250		
30		#4@12" O.C-Ties Reinforcement: (Zone-10) -10-#8 Bars-Vertical (cellar to 1st) -8-#8 Bars-Vertical (1st-3rd Floor) -6-#8 Bars-Vertical (3rd to Roof)		1	10%	1	TONs	\$ 1,250		
		#4@12" O.C-Ties			10%	1		\$	1,483	

SR #	CSI SECT	DESCRIPTION	Drawing Reference	QUANTITY	WASTAGE (10%)	QTY WITH WASTAGE	UNIT OF MEASUREMENT	UNIT COST	TOTAL ITEM COST	TOTAL TRADE COST
31		Reinforcement: (Zone-13) -12#8 Bars-Vertical (cellar to 2nd) -#4@12" O.C-Ties		0	10%	1	TONs	\$ 1,250	\$ 661	
		COLUMNS								
		Column #1								
32		24"x12" Concrete Column		4	10%	4	CY	\$ 180	\$ 792	
		Shear Reinforcement:								
33		Ties Rebars- #4		381	10%	419	LBs	\$ 1	\$ 302	
34		Rebars- #7		613	10%	674	LBs	\$ 1	\$ 485	
35		Rebars- #9		204	10%	224	LBs	\$ 1	\$ 162	
36		5/8" Dia x22-1/2"Hx84"L		24	10%	26	EA	\$ 18	\$ 475	
		Main Reinforcement:								
37		6-#7 Bars		699	10%	769	LBs	\$ 1	\$ 554	
		Column #2								
38		24"x12" Concrete Column		6	10%	7	CY	\$ 180	\$ 1,188	
		Shear Reinforcement:								
39		Ties Rebars- #4		568	10%	625	LBs	\$ 1	\$ 450	
40		Rebars- #7		920	10%	1012	LBs	\$ 1	\$ 729	
41		Rebars- #9		357	10%	393	LBs	\$ 1	\$ 283	
		Main Reinforcement:								
42		6-#7 Bars		1042	10%	1146	LBs	\$ 1	\$ 825	
		Column P-1								
43		12"x12" Concrete Column		0	10%	0	CY	\$ 180	\$ -	
		Shear Reinforcement:								
44		Ties Rebars- #4		48	10%	53	LBs	\$ 1	\$ 38	
45		Rebars- #7		123	10%	135	LBs	\$ 1	\$ 97	
		Main Reinforcement:								
46		4-#7 Bars		98	10%	108	LBs	\$ 1	\$ 78	
		Column P-2								
47		24"x12" Concrete Column		0	10%	0	CY	\$ 180	\$ -	
		Shear Reinforcement:								
48		Rebars- #7		104	10%	114	LBs	\$ 1	\$ 82	
		Main Reinforcement:								
49		4-#7 Bars		98	10%	108	LBs	\$ 1	\$ 78	
		SLABS & ASSOCIATED ITEMS								
		First Floor								
49		8"TT Slab 5'x10'x5' - 5000 PSI		335	10%	369	SF	\$ 4	\$ 1,327	
50		10 MIL Vapor Barrier		335	10%	369	SF	\$ 1	\$ 251	
51		6"TT Gravel Fill Under Slab		12	10%	14	CY	\$ 25	\$ 341	
52		Reinforcement: -#4@12" O.C E.W		448	10%	492	LBs	\$ 1	\$ 354	
53		(6"W) Concrete Stairs and 4" Concrete Slab		1	10%	1	CY	\$ 98	\$ 76	
54		6x6-W4.0xW4.0 WWR		36	10%	40	SF	\$ 1	\$ 20	
55		Reinforcement: #4 Rebars		65	10%	72	LBs	\$ 1	\$ 51	
56		400 High Density Extruded Polystyrene Insulation-5'Deep		36	10%	40	SF	\$ 4	\$ 143	
57		(3'6"W) Concrete Stairs and 4" Concrete Slab		1	10%	1	CY	\$ 98	\$ 59	
58		6x6-W4.0xW4.0 WWR		40	10%	44	SF	\$ 1	\$ 22	
59		Reinforcement: #4 Rebars		70	10%	77	LBs	\$ 1	\$ 55	
60		400 High Density Extruded Polystyrene Insulation-5'Deep		40	10%	44	SF	\$ 4	\$ 158	
61		(12"x12") Grade Beam GB-1		1	10%	1	CY	\$ 98	\$ 84	
62		Reinforcement: -2#5 Top & Bottom Bars -#4@4" O.C Stirrups		254	10%	279	LBs	\$ 1	\$ 201	
63		(24"x24") Grade Beam SB-1		2	10%	3	CY	\$ 98	\$ 264	
64		Reinforcement: -3#9 Top & Bottom Bars -#4@4" O.C Stirrups		272	10%	299	LBs	\$ 1	\$ 216	
65		10"TT Concrete Slab S2 -5000 PSI		6210	10%	6831	SF	\$ 6	\$ 40,986	
66		#5@12" O.C E.W T&B		13	10%	14	TONs	\$ 1,250	\$ 17,795	
67		Addition Reinforcement #7 and #9 Bars		1	10%	1	TONs	\$ 1,250	\$ 940	
		2nd Floor								
68		14"TT Concrete Slab S3 -5000 PSI		1945	10%	2140	SF	\$ 8	\$ 16,046	
69		#5@12" O.C E.W T&B		4	10%	4	TONs	\$ 1,250	\$ 5,573	
70		Addition Reinforcement #7		1	10%	1	TONs	\$ 1,250	\$ 1,017	
71		24"TT Concrete Slab S4 -5000 PSI		5248	10%	5773	SF	\$ 9	\$ 49,069	
72		#5@12" O.C E.W T&B		11	10%	12	TONs	\$ 1,250	\$ 15,038	
73		Addition Reinforcement #9 Bars		1	10%	1	TONs	\$ 1,250	\$ 1,290	

SR #	CSI SECT	DESCRIPTION	Drawing Reference	QUANTITY	WASTAGE (10%)	QTY WITH WASTAGE	UNIT OF MEASURE	UNIT COST	TOTAL ITEM COST	TOTAL TRADE COST
3RD Floor										
74		8" T Concrete Slab S1-5000 PSI		5022	10%	5524	SF	\$ 5	\$ 29,831	
75		#4@12" O.C E.W T&B		7	10%	7	TONs	\$ 1,250	\$ 9,225	
76		Addition Reinforcement #7		0	10%	1	TONs	\$ 1,250	\$ 648	
77		#5 @12" O.C Hot Dip Galvanized Top Bars		0	10%	0	TONs	\$ 1,250	\$ 115	
Roof										
78		10" T Concrete Slab S2-5000 PSI		345	10%	380	SF	\$ 6	\$ 2,277	
79		#5@12" O.C E.W T&B		1	10%	1	TONs	\$ 1,250	\$ 989	
80		Addition Reinforcement #7		0	10%	0	TONs	\$ 1,250	\$ 26	
81		(24"x18") Concrete Beam B1		2	10%	2	CY	\$ 98	\$ 240	
82		Reinforcement: 3#8 Bars T&B		320	10%	352	LBs	\$ 1	\$ 254	
Bulkhead Roof										
83		10" T Concrete Slab S2-5000 PSI		1270	10%	1397	SF	\$ 6	\$ 8,382	
84		#5@12" O.C E.W T&B		3	10%	3	TONs	\$ 1,250	\$ 3,639	
85		Addition Reinforcement #7		0	10%	0	TONs	\$ 1,250	\$ 539	
86		Addition Reinforcement #5		0	10%	0	TONs	\$ 1,250	\$ 23	
87		4" T Concrete Mechanical Equipment Pad		26	10%	29	SF	\$ 2	\$ 46	
88		Reinforcement: #4@12" O.C E.W		40	10%	44	LBs	\$ 1	\$ 32	
		-#4 Hooked Bars @24" O.C								
89		8" T Concrete Slab S1-5000 PSI		108	10%	119	SF	\$ 5	\$ 642	
90		#4@12" O.C E.W T&B		0	10%		TONs	\$ 1,250	\$ 198	
PILES										
91		30"Dx9" Dia Concrete Piles -75KSI=36 EA		19	10%	21	LF	\$ 180	\$ 3,497	
92		Reinforcement=Assumed			10%	2	TONs	\$ 1,250	\$ 2,750	
PILE CAPS										
93		11"x8"11"x2'8" T Pile Cap PC-6		1	10%	11	CY	\$ 180	\$ 2,034	
94		Reinforcement: Bottom: 9-#9 & #8@12" O.C					TONs	\$ 1,250		
		Top: 8-#9 & #8@12" O.C			10%	1		\$	\$ 773	
95		11"x8"11"x2'8" T Pile Cap PC-20		33	10%	36	CY	\$ 180	\$ 6,461	
96		Reinforcement: Bottom: 9-#9 & #8@12" O.C		1.4	10%	2	TONs	\$ 1,250		
		Top: 8-#9 & #8@12" O.C						\$	\$ 1,937	
MISC.										
97		14"Wx12"D Drain Trench		52	10%	57	LF	\$ 58	\$ 3,318	
STAIRS										
98		(3'0" W) Conc. Stairs Type A		21	10%	23	cy	\$ 180	\$ 4,070	
99		Reinforcement		2	10%	2	TONs	\$ 1,250	\$ 2,063	
100		(3'0" W) Conc. Stairs Type B		25	10%	27	cy	\$ 180	\$ 4,884	
101		Reinforcement		2	10%	2	TONs	\$ 1,250	\$ 2,063	
102		(3'0" W) Conc. Stairs Type C		4	10%	5	cy	\$ 180	\$ 814	
103		Reinforcement		0	10%	0	TONs	\$ 1,250	\$ 413	
104		(3'0" W) Conc. Stairs Type D		4	10%	4	cy	\$ 180	\$ 770	
105		Reinforcement		0	10%	0	TONs	\$ 1,250	\$ 275	
SUB TOTAL									\$ 543,731	\$ 543,731
OVERHEAD & PROFIT (25%)									25% \$ 135,933	\$ 135,933
TOTAL BID									\$ 679,664	\$ 679,664
PREPARED FOR :										
PREPARED BY :										
Notes										
This estimate is based on real market prices that are regularly updated by our team persons through market surveys.										